



DEANE

ROADS & BRIDGES



A Southbound view of the scheme showing accommodation works

A Northbound view of the A5 Leckpatrick scheme



SITE

A5 Victoria Road Realignment,
Leckpatrick

CLIENT

DRDNI Roads Service
Western Division

CONSULTANT

DRDNI Roads Design

DURATION

52 Weeks

CONTRACT VALUE

£ 2,300,000

This scheme is at Ballymagorry, located approximately 4km north of Strabane, Co. Tyrone, on the A5 to Derry City. The widening and realignment extended 2km north of Ballymagorry village with the widening specifically designed to give a crawler lane for slow moving traffic ascending from the Foyle River valley. The A5 carries approximately 9,500 vehicles per day. The work entailed the construction of approximately 800m of new carriageway, adjacent for the most part to the existing carriageway and the realignment of 1200m of existing carriageway. There was a further 300m of new minor carriageway works to realign adjacent side roads.

Associated works involved the provision of additional services and alternation of existing services, drainage and extensive accommodation works for both residential and farm-land areas. Due to restrictions in the contract, limiting the use of traffic control by temporary traffic lights or stop/go systems and with no traffic diversions away from the site acceptable, an extensive Traffic/Pedestrian Safety Management system had to be maintained during the course of the scheme.

